

Ref: CBBL/GSD/RFQ/2022/0042

Date: November 23, 2022

Subject: Tender and Enlistment for Interior Decoration & Electrical Repair Maintenance Works for Community Bank Bangladesh Limited

Dear Sir:

Community Bank Bangladesh Limited invites financial proposals for **Interior Decoration & Electrical Repair Maintenance Works** for Community Bank Bangladesh Limited mentioned in below from reputed Companies.

Quotation Format for Regular/Monthly/On call Services:

Tender and Enlistment for Interior Decoration and Electrical Repair Maintenance Works for Community Bank Bangladesh Limited			
SN	ITEM DESCRIPTION	UNIT	UNIT PRICE
A. CIVIL WORKS			
1	5" THICK BRICK WORK Brick work with 1st class bricks of one brick width [±5"] in cement mortar (1:4) in exterior or interior walls in/c filling the interstices with mortar, racking out joints cleaning and soaking the bricks at least for 24 hours before use and necessary scaffolding, curing at least for 7 days etc. complete in all respect as per design drawing and direction of Consultant / Bank Authority.	Sft	
2	10" THICK BRICK WORK Brick work with 1st class bricks of one brick width [±10"] in cement mortar (1:4) in exterior or interior walls in/c filling the interstices with mortar, racking out joints cleaning and soaking the bricks at least for 24 hours before use and necessary scaffolding, curing at least for 7 days etc. complete in all respect as per design drawing and direction of Consultant / Bank Authority.	Sft	
3.1	R.C.C WORK [LINTEL/SLAB/WALL] Reinforced cement concrete works (1:2:4) having minimum crushing strength 18 Mpa (cylinder) at 28 days with cement, best quality coarse sand [50% quantity of best local sand (F.M.-1.5) and 50% quantity of Sylhet sand or coarse sand of equivalent (F.M.- 2.5)] picked jhama chips including breaking chips and screening, centering, shuttering, supplying polythene sheet for making shuttering leak proof, placing of rod in position, mixing the aggregates, casting in forms, compacting & curing for 15 days if possible including the cast of reinforcement and its fabrication as per design drawing and direction of Consultant / Bank Authority.	Cft	
3.2	R.C.C WORK [Vault & Locker] Reinforced cement concrete works (1:2:4) having minimum crushing strength 18 Mpa (cylinder) at 28 days with cement, best quality coarse sand [50% quantity of best local sand (F.M.-1.5) and 50% quantity of Sylhet sand or coarse sand of equivalent (F.M.- 2.5)] Brick Chips including screening, centering, shuttering, supplying polythene sheet for making shuttering leak proof, placing of rod in position, mixing the aggregates, casting in forms, compacting & curing for 15 days if possible including the cost of reinforcement and its fabrication as per design drawing and direction of Consultant / Bank Authority. Use 12mm @ 6" c/c both way @ double layer for wall and 12mm @ 4" c/c both way @ single layer for floor & roof as per design drawing and direction of Consultant / Bank Authority.	Cft	

4	C.C WORK [Cement concrete works] (1:2:4) with cement, best quality coarse sand [50% quantity of best local sand (F.M.-1.5) and 50% quantity of Sylhet sand or coarse sand of equivalent (F.M.- 2.5)] Brick Chips including screening, centering, shuttering, supplying polythene sheet, mixing the aggregates, casting in forms, compacting & curing for 15 days if possible including the cast of reinforcement and its fabrication as per design drawing and direction of Consultant / Bank Authority.	Cft	
5	BRICK FLAT SOLING Single layer of brick flat soling in foundation or in floor with 1st class or picked jhama bricks in/c preparation of bed and filling the interstices with local sand, leveling, ramming in/c the supply of water, polythene, electricity and other charges and costs of tools and plants etc. all complete as per design drawing and direction of Consultant / Bank Authority.	Sft	
6	FLOOR CHIPPING Chipping and cleaning the floor before patent stone casting and mosaic work or other finishing materials used. The chipping must be smoothly with sharpen chisel and clean all sand cement and other debris to a suitable place out side of site etc. Complete in all respect as per design drawing and direction of Architect/ Authority.	Sft	
7	PATENT STONE Artificial stone flooring work, at all heights, 38 mm thick in 1:2:4 using 50% coarse sand (Min F .M. 2.5) 50% medium sand of Minimum F .M. 1.5 as fine aggregate and 1/2" down graded brick chips as coarse aggregate including breaking the bricks into chips, screening and washing of chips and sand, compacting, conveying, placing the concrete, curing for at least 7 (seven) days etc. Complete in all respect as per design drawing and direction of Architect/ Authority.	Sft	
8	NEAT CEMENT FINISH Neat Cement Finishing Work simultaneously done on Patent stone/concrete surface using cement screened through fine cloth in the form of cement slurry, rubbing smooth with steel trowel, scaffolding, curing for 10 days etc. complete in all respect as per design drawing and direction of Consultant / Bank Authority.	Sft	
9.1	CEMENT PLASTER Minimum 1/2" thick cement plaster [1:5] to wall/ceiling both inner and outer surface, finishing the corners and edges in/c cleaning the surface, scaffolding and curing at least for 7 days etc. complete in all respect as per design drawing and direction of Consultant / Bank Authority.	Sft	
9.2	CEMENT PLASTER (Vault & Locker) Minimum 3/4" thick cement plaster [1:5] to wall/ceiling both inner and outer surface, finishing the corners and edges in/c cleaning the surface, scaffolding and curing at least for 7 days etc. complete in all respect as per design drawing and direction of Consultant / Bank Authority.	Sft	
10	DISMANTLING [All necessary dismantling to complete the project] Dismantling some existing Brick works, CC works, RCC works, Plaster works, Mosaic works, Opening of some Doors/Windows/Shutters, Grills etc. as per direction of the Architect/Authority and removing the debris to a safe distance to be shown by the Authority from the site by the contractor at his own cost and responsibility. Proper care and precautions should be taken for the safety of the Building including its services [viz: Structural, Plumbing & Sanitary, Electrical, Computer Network etc.] during dismantling.		
10.1	RCC work	Cft	
10.2	CC work	Cft	
10.3	5" Brick work	sft	
10.4	10" Brick work	Cft	
10.5	Tiles work	Sft	

11	Earth Cutting	Cft	
12	Sand Filling	Cft	
13	Earth Filling	Cft	
B. MS/SS/ACP WORKS			
1	ROLLING SHUTTER Supply, fitting & fixing steel rolling shutter made of strips imported G.P. sheet of approved thickness and quality including locking arrangement and paint finish etc. complete in all respect as per design drawing and direction of Consultant / Bank Authority.	Sft	
2	ROLLING SHUTTER [ROD]: Supply, fitting & fixing steel manually operated rolling shutter made of solid MS rod of 10mm dia bend in wave shape and connected to each other with MS interlocked hinges, top hanged and easily run inbetween two sturdy MS guide rails, including concealed type locking arrangement and paint finish etc. complete in all respect as per design drawing and direction of Architect/ Authority.	sft	
3	ALUMINUM COMPOSITE PANEL Supply, fitting & fixing of 4mm thick aluminum composite panel (Stainless Steel Hair line texture) or approved color and quality cladded on standard and necessary aluminum framing etc. complete in all respect as per design drawing and direction of Consultant / Bank Authority.	Sft	
4	MS WINDOW GRILL Supplying, fitting and fixing window grill made by 1/2" x 1/2" solid MS square bar placed 4" C/C horizontally and 1'-0" to 1'-6" C/C vertically, properly fabricated and welded, clamped within the masonry opening, in/c cutting holes for fixing etc. painting 3 coats with approved color synthetic enamel paint of "Berger" brand over a coat of anticorrosive painting in/c. cleaning, finishing, grinding putty works etc. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Sft	
5	COLLAPSIBLE SHUTTER Supplying and fixing collapsible shutters made of 1"x1"x 1/4" MS angle placed @+4" c/c vertically and connecting the same with the same with each other with 1"x1/4" M.S. flat bar scissors 18" to 20" long provided in 3 rows in/c. cutting the different MS members to required sizes, fabricating, welding, riveting with required size rivets, providing required size wheels, pulling handles, suitable locking arrangements (2 nos.) and finally placing the same in position in between 2 nos. 2"x2"x1/4" M.S. Tee rail fitted and fixed at top and bottom with R.C.C lintel/beam floors and side walls with required nos. 6" to 9" long 1 1/4"x1/4" MS flat bar clamps one end welded with the shutter member and the other end bifurcated and embedded in C.C. (1:2:4) in/c. cutting holes etc. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Sft	
6	STAINLESS STEEL RAILING Supplying, fitting and fixing stainless steel railing made by 2" dia handrail, 3 nos. horizontal members of 3/4" dia and vertical members of 3/4" placed at a distance + 2'-0" all welded perfectly and fixed by the side of the wooden stair, in/c painting 3 coats with approved color synthetic enamel paint of "Berger" brand over a coat of anticorrosive painting in/c cleaning and polishing etc. complete in all respect as per design drawing and direction of Consultant / Bank Authority.	Sft	
7	DESIGN MS PARTITION Supply, fitting & fixing of MS design partition made of 2mm thick 50mmX25mm MS box frame with 10mm glass & Heat paint finish etc.(same as Corporate branch) complete in all respect as per design drawing and direction of Consultant / Bank Authority.	Sft	
8	SS Q-STAND WITH CHAIN (6 nos Post & 4 nos chain) Supplying, fitting and fixing stainless steel Q-stand made by 3" dia with chain approved color, cleaning and polishing etc. complete in all respect as per design drawing and direction of Consultant / Bank Authority.	Set	

9	<p>MS STEEL DOOR (Size:1050mmX2100mm clear): Supply, fitting and fixing of MS Steel Door, Door frame made of 100mm X 50mm MS box, door shutter made of 38mm MS angle cover with 3mm MS sheet (welded) with 01 Security & 01 master lock with handle, view finder setting the Door frame properly, rust removing & grinding the joints, heavy type clamps fitted and fixed with the outer frame of the main gate, the clamp being embedded in RCC, RC Core pillar with cement concrete (1:2:4) in masonry including cutting holes and mending good the damages, finishing, 02 nos stopper (China-Half round SS, rubber coating), 150mm long tower bolt(Imported), curing including fabrication, riveting, welding as and where necessary etc. including painting 03 coats of enamel paint over a coat of anticorrosive priming etc. all complete as per direction and full satisfaction of the Consultant / Bank Authority.</p>	Nos	
C. PAINT WORKS			
1	<p>PLASTIC PAINT (White & Roof Top Black) Plastic painting of 'Berger' brand of approved color to wall minimum 3 coats with lime putty work, cleaning, sand papering the surfaces in/c. necessary scaffolding etc. complete in all respect as per direction of Consultant / Bank Authority.</p>	Sft	
2	<p>ENAMEL PAINT Synthetic Enamel paint of 'Berger' brand of approved color to wall, ceiling, wooden surfaces, iron grills, shutters etc. minimum 3 coats over a coat of priming including cleaning, finishing and polishing with sand paper and necessary scaffolding etc. complete in all respect as per direction of Consultant / Bank Authority.</p>	Sft	
3	<p>OUTSIDE 'WEATHER COAT' PAINT Weather Coat painting of 'Berger' brand of approved color to wall minimum 3 coats in/c preparing the under surface, cleaning, sand papering the surfaces in/c. necessary scaffolding etc. complete in all respect as per direction of Consultant / Bank Authority.</p>	Sft	
4	<p>GRANULAR PAINT (HERITAGE) All complete in all respect as per direction of Consultant / Bank Authority.</p>	Sft	
5	<p>TEXTURE PAINT (CONMIX) All complete in all respect as per direction of Consultant / Bank Authority.</p>	Sft	
D. TILE/MARBLE & FLOOR FINISH WORKS			
1	<p>MIRROR POLISHED HOMOGENEOUS FLOOR TILES [IMPORTED, APPROVED COLOR] Supplying, fitting and fixing homogeneous floor tiles [Imported] of 24" x 24" size and quality on 20 mm thick cement mortar (1:2) base or by 'CONMIX' base and raking out the joints with white cement and colored pigment including cutting by electric disk cutter and laying tiles in proper way in/c chipping or dismantling of existing floor if necessary and finishing with care etc. complete in all respect as per design drawing and direction of Consultant / Bank Authority.</p>	Sft	
1.1	<p>MIRROR POLISHED HOMOGENEOUS FLOOR TILES [RAK/DBL/AKIJ, APPROVED COLOR] Supplying, fitting and fixing homogeneous floor tiles [Imported] of 24" x 24" size and quality on 20 mm thick cement mortar (1:2) base or by 'CONMIX' base and raking out the joints with white cement and colored pigment including cutting by electric disk cutter and laying tiles in proper way in/c chipping or dismantling of existing floor if necessary and finishing with care etc. complete in all respect as per design drawing and direction of Consultant / Bank Authority.</p>	Sft	

2	HOMOGENEOUS FLOOR TILES [RAK,CBC,AKIJ] Supplying, fitting and fixing homogeneous floor tiles of 16" x16" size and quality on 20 mm thick cement mortar (1:2) base or by 'CONMIX' base and raking out the joints with white cement and colored pigment including cutting by electric disk cutter and laying tiles in proper way in/c chipping or dismantling of existing floor if necessary and finishing with care etc., complete in all respect as per design drawing and direction of Consultant / Bank Authority.	Sft	
3	STAIR STEP TILES [RAK,CBC,AKIJ] Supplying, fitting and fixing homogenous stair step tile Approved color of 12" x 12" size & quality on at least ¾" thick cement mortar (1:2) base or by 'CONMIX' base and raking out the joints with white cement and colored pigment including cutting by electric disk cutter and laying tiles in proper way and finishing with care etc. complete in all respect as per design drawing and direction of Consultant / Bank Authority.	Sft	
4.1	CERAMIC WALL TILES [RAK,CBC,AKIJ With Border] Supplying, fitting and fixing colored glazed wall tiles Approved color of approved size- 13"x20" & quality on 20 mm thick cement mortar [1:2] base and raking out the joints with white cement including cutting and laying the tiles in proper way and finishing with care etc. complete in all respect as per design drawing and direction of Consultant / Bank Authority.	Sft	
4.2	CERAMIC WALL TILES [RAK,CBC,AKIJ With Border] Supplying, fitting and fixing colored glazed wall tiles Approved color of approved size- 8"x12" & quality on 20 mm thick cement mortar [1:2] base and raking out the joints with white cement including cutting and laying the tiles in proper way and finishing with care etc. complete in all respect as per design drawing and direction of Consultant / Bank Authority.	Sft	
4.3	CERAMIC WALL TILES [RAK,CBC,AKIJ With Border] Supplying, fitting and fixing colored glazed wall tiles Approved color of approved size- 12"x16" & quality on 20 mm thick cement mortar [1:2] base and raking out the joints with white cement including cutting and laying the tiles in proper way and finishing with care etc. complete in all respect as per design drawing and direction of Consultant / Bank Authority.	Sft	
5.1	CERAMIC WALL TILES [RAK,CBC,AKIJ] Supplying, fitting and fixing colored glazed wall tiles Approved color of size (13"x20") & approved quality & model on 20 mm thick cement mortar [1:2] base and raking out the joints with white cement including cutting and laying the tiles in proper way and finishing with care etc. complete in all respect as per design drawing and direction of Consultant / Bank Authority.	Sft	
5.2	CERAMIC WALL TILES [RAK,CBC,AKIJ] Supplying, fitting and fixing colored glazed wall tiles Approved color of size (8"x12") & approved quality & model on 20 mm thick cement mortar [1:2] base and raking out the joints with white cement including cutting and laying the tiles in proper way and finishing with care etc. complete in all respect as per design drawing and direction of Consultant / Bank Authority.	Sft	
5.3	CERAMIC WALL TILES [RAK,CBC,AKIJ] Supplying, fitting and fixing colored glazed wall tiles Approved color of size (12"x16") & approved quality & model on 20 mm thick cement mortar [1:2] base and raking out the joints with white cement including cutting and laying the tiles in proper way and finishing with care etc. complete in all respect as per design drawing and direction of Consultant / Bank Authority.	Sft	

6	GRANITE & MARBLE WORKS Supplying, fitting and fixing following stone on walls/columns over minimum 18 mm thick cement mortar [1:2] in/c cutting, grinding and polishing the stones, setting in position keeping horizontal & Vertical alignment correct, filling the joints with same color putty, making grooves, finishing with care, etc. complete in all respect as per design, drawing & direction of Architect/ Authority. Note: [1] Quality, color & texture of Granite stone must be approved before fixing [2] There may be combination of shades for claded materials. complete in all respect as per design drawing and direction of Consultant / Bank Authority.		
	10/12 mm Granite [1'-0" x 2'-0"] / IMPORTED	Sft	
	18/20 mm Marble [required size] / IMPORTED	Sft	
7	SLATE STONE CLADDING WORKS Supplying, fitting and fixing Slate Stone of approved size (12"x24") and quality on at least ¾" thick cement mortar (1:2) base or by 'CONMIX' base and raking out the joints with white cement and colored pigment including cutting by electric disk cutter and laying Stone in proper way. complete in all respect as per design drawing and direction of Consultant / Bank Authority.	Sft	
8	PAVEMENT TILES WORKS Machine made pavement tiles/block made by Mirpur Ceramic/Concord/Unik/Others of approved quality and color on minimum 20 mm thick cement sand mortar [1:3] in/c raking out joints, cutting the blocks to required size wherever necessary, soaking the same 24 hours before use in/c high class pointing in cement mortar [1:2], cleaning, curing at least 7 days etc. complete in all respect as per design drawing and direction of Consultant / Bank Authority.	Sft	
9	RUSTIC TILES WORK ON WALL Supply, fitting & fixing of 300mmX600m (Malaysia) rustic tiles in wall of approved color with 20 mm thick cement sand (F.M. 1:2) mortar (1:3) base and raking out the joints with respective joint filter and binder including cutting, laying and hire charge of machine and finishing with care etc including water, electricity and other charges All complete as per Bank standard and full satisfaction of the Consultant / Bank Authority.	Sft	
E. PLUMBING & SANITARY WORKS			
1	COMBI COMMODE SET Supplying, fitting and fixing foreign made approved colored combi commode in/c all if its original fittings viz. flushing arrangements, seat cover fixing screws/bolts, preparing the base of commode with cement concrete and with wire net or rods, if necessary, in/c making holes wherever required and mending good the damages and fitting, fixing complete with all necessary fittings and connection as per design, drawing and direction of Consultant / Bank Authority. [TOTO-Model-C320RE/C325RE]	Set	
2	COMBI COMMODE SET Supplying, fitting and fixing foreign made approved colored combi commode in/c all if its original fittings viz. flushing arrangements, seat cover fixing screws/bolts, preparing the base of commode with cement concrete and with wire net or rods, if necessary, in/c making holes wherever required and mending good the damages and fitting, fixing complete with all necessary fittings and connection as per design, drawing and direction of Consultant / Bank Authority. [RAK-carela]	Set	
3	PAN WITH LOWDOWN [RAK] Supplying, Fitting and fixing approved color oriental pan with foot rest including ceramic lowdown, best quality internal fittings, best quality 30 mm dia concealed PVC flush pipe with brass coupling and preparing the base of pan with cement concrete and with wire net or rods, if necessary, in/c making holes wherever required and mending good the damages and fitting, fixing complete with all necessary fittings and connection as per design, drawing and direction of Consultant / Bank Authority.	Set	

4	CABINET/PEDESTAL BASIN Supplying, fitting and fixing Foreign made approved colored glazed vitreous Basin [Pedestal/Cabinet type] in/c fitting, fixing the same in position with heavy type C.I. brackets, in/c fitting and fixing all necessary fittings, chain plug in/c making holes in walls and floors, mending good the damages etc., complete in all respect as per design drawing and direction of Consultant / Bank Authority. [TOTO-Model-LW565]	Set	
5	CABINET/PEDESTAL BASIN Supplying, fitting and fixing Foreign made approved colored glazed vitreous Basin [Pedestal/Cabinet type] in/c fitting, fixing the same in position with heavy type C.I. brackets, in/c fitting and fixing all necessary fittings, chain plug in/c making holes in walls and floors, mending good the damages etc., complete in all respect as per design drawing and direction of Consultant / Bank Authority. [RAK- sinthia]	Set	
6.1	REQUIRED PLUMBING AND SANITARY WORKS i. Supply, fitting and fixing of 25mm/18mm G.I./Upvc pipe with all general fitting such as bend, elbow, socket, reducing socket, Tee, unions, jam-nuts, gate valve for each toilet and kitchen including cutting trenches where necessary and fitting the same with earth duly rammed and fixing in walls with holder, bats and making hole in floor, walls and consequent mending good the damages etc all complete from building main line to the desired areas of usage.	Job	
6.2	REQUIRED PLUMBING AND SANITARY WORKS ii. Supply fitting and laying up to depth of invert 100mm inside dia best quality UPVC C grade pressure soil pipe having specific gravity 1.3-1.45 and other physical, chemical, thermal, fire resistivity properties etc as per BSTI approved manufacturer standards or ASTM, BS/ISO/IS standards fitted & fixed in position with sockets, bends, door tee, elbow, Tee with all accessories such as solvent cement, round grating/domed roof grating etc from the available line to wash rooms to the disposal line all complete as per Bank standard and full satisfaction of the Consultant / Bank Authority.	Job	
7	STAINLESS STEEL SINK Supplying, fitting and fixing best quality Gazi/RFL stainless steel kitchen sink of 20" X 40" size [single bowl single tray] fixing the same on R.C.C tiled counter with heavy type C.I brackets 30 mm dia PVC waste water pipe with brass coupling in/c fitting and fixing the sink waste in/c making holes in walls and floors and fitting with rowel plugs, screws and mending good the damages etc. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Set	
8.1	URINAL Supply, fitting & fixing of urinal set (RAK/Victory / Huida) of approved color with other fittings etc. complete in all respect as per design drawing and direction of Consultant / Bank Authority.	Set	
8.2	URINAL Supply, fitting & fixing of urinal set (Toto/Coto) of approved color with other fittings etc. complete in all respect as per design drawing and direction of Consultant / Bank Authority.	Set	
9	MISCELLANEOUS TOILET FITTINGS [Local / Foreign made] Supplying, fitting and fixing best quality local / foreign made following items of approved brand ['Nazma'-Local / Approved - Foreign] in/c making holes in walls by Electric Hammer Drill Machine, in/c Supplying, fitting and fixing clamps, rowel plugs and screws of appropriate size, other necessary consumables in/c making holes in walls and floors [where necessary] and mending good the damages etc. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.		
9.1	TOWEL RAIL [Haibali] Best quality available C.P. towel rail of 600 mm X 20 mm size with C.P. holder, screws etc. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Nos	
9.2	ANGLE STOP COCK [Sharif/Nazma] Best quality available 12mm heavy type C.P concealed angle stop cock. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Nos	

9.3	2 IN 1 BIB COCK [Sharif/Nazma] Best quality available heavy type 12 mm C.P concealed bib cock. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Nos	
9.4	PILLAR COCK [Sharif/Nazma] Best quality available heavy type 12 mm C.P pillar cock. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Nos	
9.5	BIB COCK [Sharif/Nazma] Best quality available heavy type 12 mm C.P concealed bib cock. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Nos	
9.6	SINK COCK [Sharif/Nazma] Best quality available heavy type 12 mm C.P concealed moving sink cock. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Nos	
9.7	HAND SHOWER [Haibali] Supplying, fitting and fixing best quality local made hand shower approved quality complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Nos	
9.8	MAGIC PIPE [Haibali] Best quality available heavy type Magic pipe. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Nos	
9.9	SOAP TRAY [Haibali] Best quality available C.P Soap tray of standard size in/c all fittings etc. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Nos	
9.10	CONNECTION PIPE [Haibali] Best quality available 12 mm dia plastic connection pipe of required length with brass coupling at both end. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Nos	
9.11	PAPER HOLDER [Haibali] Best quality available heavy type C.P. paper holder in/c one roll of paper. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Nos	
9.12	FLOOR GRATING [Haibali] Best quality available stainless steel made square type floor grating in traps or in drains. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Nos	
9.13	GATE VALVE [ITAP brand, Pedrollo] Supplying, fitting & fixing best quality Italian made 'ITAP' brand ½" dia gate valve complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Nos	
9.14	BASIN MIRROR Supplying, fitting and fixing best quality mirror made by float glass on wall fixed by approved type glass holder complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Sft	
9.15	LIQUID SOAP CASE Supply, fitting & fixing of Liquid soap case (Imported) of approved color with necessary hardware etc. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Nos	
9.16	COAT HOOK Supply, fitting & fixing of COAT HOOK (Imported) of approved color with necessary hardware etc. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Nos	
F. ELECTRICAL WORKS			
1	Supply, installation, testing and commissioning of under noted fixtures with the help of necessary wires including all required materials as per the satisfaction of Consultant / Bank Authority.		

1.1	LED SINGLE TUBE LIGHT [Energypac or Equivalent, Size: 4'- 0"] approved type down tube light shade [reflector] with minimum 40 watt Energypac /Equivalent LED Tube light in/c supply of all necessary consumable materials, compatible to local voltage variation, complete in all respect in/c testing & commissioning, as per design, drawing and direction of Consultant / Bank Authority.	Nos	
1.2	LED SINGLE TUBE LIGHT [Energypac or Equivalent, Size: 2'- 0"] approved type down tube light shade [reflector] with minimum 20 watt Energypac /Equivalent LED Tube light in/c supply of all necessary consumable materials, compatible to local voltage variation, complete in all respect in/c testing & commissioning, as per design, drawing and direction of Consultant / Bank Authority.	Nos	
1.3	LED PANEL LIGHT FITTING [Energypac or Equivalent, Size: 6"dia (Square/Round)] approved type down light shade [reflector] with minimum 12 watt Energypac /Equivalent LED light in/c supply of all necessary consumable materials, compatible to local voltage variation, complete in all respect in/c testing & commissioning, as per design, drawing and direction of Consultant / Bank Authority.	Nos	
1.4	LED PANEL LIGHT FITTING [Energypac or Equivalent, Size: 8"dia (Square/Round)] approved type down light shade [reflector] with minimum 18 watt Energypac /Equivalent LED light in/c supply of all necessary consumable materials, compatible to local voltage variation, complete in all respect in/c testing & commissioning, as per design, drawing and direction of Consultant / Bank Authority.	Nos	
1.5	LED PANEL LIGHT FITTING [Energypac or Equivalent, Size: 1'x1'] approved type down light shade [reflector] with minimum 24 watt Energypac /Equivalent LED light in/c supply of all necessary consumable materials, compatible to local voltage variation, complete in all respect in/c testing & commissioning, as per design, drawing and direction of Consultant / Bank Authority.		
1.6	LED PANEL LIGHT FITTING [Energypac or Equivalent, Size: 2'x2'] approved type down light shade [reflector] with minimum 36 watt Energypac /Equivalent LED light in/c supply of all necessary consumable materials, compatible to local voltage variation, complete in all respect in/c testing & commissioning, as per design, drawing and direction of Consultant / Bank Authority.	Nos	
1.7	IMPORTED HANGING TUBE LIGHT SHADE [4'-0" LONG] Supply, fitting & fixing of imported hanging tube light shade with powder coated paint finish, hanging with rod, led tube light (approved sample) with other necessary accessories etc. complete in all respect in/c testing & commissioning, as per design, drawing and direction of Consultant / Bank Authority.	Nos	
1.8	IMPORTED HANGING DISH LIGHT Supply, fitting & fixing of imported dish light shade made with powder coated paint finish, hanging with rod, 18w LED light (approved sample) with other necessary accessories etc. complete in all respect in/c testing & commissioning, as per design, drawing and direction of Consultant / Bank Authority.	Nos	
1.9	LED STRIP LIGHT [Energypac or Equivalent] Supply, fitting, fixing of LED strip light of ,approved sample and color, 220 volt,5000 k color temperature, with all necessary hardware all hand tools and other necessary consumables. complete in all respect in/c testing & commissioning, as per design, drawing and direction of Consultant / Bank Authority.	Rft	
1.10	HALOGEN DOWN LIGHT (IMPORTED) 250w (LED) complete in all respect in/c testing & commissioning, as per design, drawing and direction of Consultant / Bank Authority.	Nos	

1.11	WALL MOUNTED BRACKET LIGHT FITTING (IMPORTED) complete in all respect in/c testing & commissioning, as per design, drawing and direction of Consultant / Bank Authority.	Nos	
1.12	LED SPOT MOVABLE LIGHT 3" : Local made approved brand spot light fitting consisting of decorative carrier, brass holder, earth terminal, necessary wiring with all consumable materials as per design, drawing and direction of Consultant / Bank Authority.	Nos	
1.13	LED SPOT PANEL LIGHT 3" : Local made approved brand spot light fitting consisting of decorative carrier, brass holder, earth terminal, necessary wiring with all consumable materials as per design, drawing and direction of Consultant / Bank Authority.	Nos	
2	Supply, installation, testing and commissioning of following items with the help of necessary wires including all required materials as per the satisfaction of Consultant / Bank Authority.		
2.1	EXHAUST FAN (National or Equivalent) supplying, fitting and fixing of following axial flow AC capacitor type wall mounted exhaust fan complete with blade, steel frame standard wall louver shutter, necessary wiring with all consumable materials as required including cutting wall and mending good the damages, complete in all respect in/c. Testing & commissioning, as per design ,drawing and direction of Consultant / Bank Authority.		
2.2	8" dia fan plastic body	Nos	
2.3	10" dia fan plastic body	Nos	
2.4	12" dia fan plastic body	Nos	
2.5	WALL MOUNTED MOVING FAN Supply and installation of 220V, 50Hz imported wall moving fan (GFC/Mira) including all standard accessories etc. All complete as per design, direction and full satisfaction of Consultant / Bank Authority.	Nos	
2.6	CEILING FAN Supply and installation of 220V, 50Hz imported wall moving fan (BRB or Equivalent Brand) of 16"/18" dia including all standard accessories etc. All complete as per design, direction and full satisfaction of Consultant / Bank Authority.	Nos	
3	PVC PIPE/PVC FLEXIBLE PIPE /PVC CHANNEL WORKS Supplying, fitting and fixing of following water grade PVC pipes or PVC channel, RFL/Bengal/Aziz brand with necessary group cutting, bend, joint box, ceiling rose, clamp, fixing materials and other accessories to complete in all respect as per design drawing and direction of Consultant / Bank Authority.		
3.1	1/2" dia PVC Pipe	Rft	
3.2	3/4" dia PVC Pipe	Rft	
3.3	1" dia PVC Pipe	Rft	
3.4	1.25" dia PVC Pipe	Rft	
3.5	1.5" dia PVC Pipe	Rft	
3.6	2" dia PVC pipe	Rft	
3.7	1/2" dia flexible Pipe	Rft	
3.8	3/4" dia flexible pipe	Rft	
3.9	1" dia flexible pipe	Rft	
3.10	1.25" dia flexible pipe	Rft	
3.11	1.5" dia flexible pipe	Rft	
3.12	2" dia flexible pipe	Rft	
3.13	3" dia flexible pipe	Rft	
3.14	3/4" dia PVC Channel	Rft	
3.15	1" dia PVC Channel	Rft	
3.16	2" dia PVC channel	Rft	

4	CABLES WORKS [BRB/BBS Brand] Supply and installation of following cables through pre laid PVC pipe/channel with all consumable materials as per design, drawing and direction of Consultant / Bank Authority.		
4.1	3/.029 or 1X1.3 rm BYA for light, fan wiring	Rft	
4.2	3/.036 or 1X2.0 rm BYA for circuit wiring	Rft	
4.3	7/.029 or 1X3.0 rm BYA for power wiring	Rft	
4.4	7/.036 or 4.5 rm BYA for air-con	Rft	
4.5	1X1.5 re BYA	Rft	
4.6	1X1.5 rm BYA	Rft	
4.7	1X2.5 rm BYA	Rft	
4.8	1X4.0 rm BYA	Rft	
4.9	1X6.0 rm BYA	Rft	
4.10	1X10 rm BYA	Rft	
4.11	1X16 rm BYA	Rft	
4.12	1CX10 rm NYY (7-w)	Rft	
4.13	1CX16 rm NYY (7-w)	Rft	
4.14	1CX25 rm NYY (7-w)	Rft	
4.15	1CX35 rm NYY (19-w)	Rft	
4.16	1CX50 rm NYY (19-w)	Rft	
4.17	3CX10 rm NYY (7-w)	Rft	
4.18	3CX16 rm NYY (7-w)	Rft	
4.19	3CX25 rm NYY (7-w)	Rft	
4.20	3CX35 rm NYY (19-w)	Rft	
4.21	3CX50 rm NYY (19-w)	Rft	
4.22	3CX25/1CX16 rm NYY (7/7-w)	Rft	
4.23	3CX35/1CX16 rm NYY 197/7-w)	Rft	
4.24	3CX50/1CX35 rm NYY (19/19-w)	Rft	
4.25	4CX10 rm NYY (7-w)	Rft	
4.26	4CX16 rm NYY (7-w)	Rft	
4.27	4CX25 rm NYY (7-w)	Rft	
4.28	4CX35 rm NYY (19-w)	Rft	
4.29	4X50 rm NYY (19-w)	Rft	
5	ELECTRICAL GANG SWITCHES Supplying, fitting and fixing 240 V, single phase Legrand (Energytac)/ABB(Multiple trading)/MK (Singapore) brand following modular Gang Switches in/c wiring conceal/surface with necessary wiring through water grade PVC pipe/channel of required size in/c supply of switches, switch box, ebonite cover, ceiling rose etc complete in all respect in/c testing & commissioning, as per design, drawing and direction of Consultant / Bank Authority.		
5.1	1-Gang Switch	Nos	
5.2	2-Gang Switch	Nos	
5.3	3-Gang Switch	Nos	
5.4	4-Gang Switch	Nos	
5.4	5-Gang Switch	Nos	
5.5	20 A DP switch	Nos	
5.6	BELL PUSH	Nos	
6	ELECTRICAL SOCKET OUTLETS Supplying, fitting and fixing 240V, single phase Legrand (Energytac)/ABB(Multiple trading)/MK (Singapore) brand following socket outlet in/c wiring conceals/surface with necessary wiring through water grade PVC pipe/channel or required size in/c supply of switches, switch box, ebonite cover, ceiling rose etc. Complete in all respect in/c testing & commissioning, as per design, drawing and direction of Consultant / Bank Authority.		

6.1	3 pin flat 13 amp+switch	Nos	
6.2	3 pin flat 13 amp+switch (double)	Nos	
6.3	3 pin round 15 amp	Nos	
6.4	2 pin socket 5amp	Nos	
6.5	16A Combined /Multi Socket	Nos	
6.6	Television socket out-let	Nos	
7	MCCB/MCB's [ABB/Legrand] Supply and installation of following SP (240V grade) TP (500 V grade) MCB/MCCB" in pre installed distribution board in/c connection with cable, cable socket, nut bolts, PIB tape etc. complete in respect providing necessary consumable in/c testing & commissioning as per design, drawing and direction of Consultant / Bank Authority.		
7.1	6 A to 40 A SP MCB-6 kA	Nos	
7.2	50 A to 63 A SP MCB-6 kA	Nos	
7.3	6 A to 40 A DP MCB-6 kA	Nos	
7.4	50 A to 63 A DP MCB-6 kA	Nos	
7.5	10 A to 40 A TP MCB-6 kA	Nos	
7.6	50 A to 63 A TP MCB-6 kA	Nos	
7.7	25 A to 100 A MCCB (TP) - Adjustable - 16kA	Nos	
7.8	125 A MCCB (TP)-Adustable-16 kA	Nos	
7.9	160 A MCCB (TP)-Adustable-36 kA	Nos	
7.10	200 A MCCB (TP)-Adustable-36 kA	Nos	
7.11	250 A MCCB (TP)-Adustable-36 kA	Nos	
8	DISTRIBUTION BOARD Supply and installation of following distribution boards [At least 2'-0" W x 2'-6" H, 5 sft] of required size made by 18 SWG B.P. sheet metal enclosed with double cover powder coated painted on outside and enamel paint on inside on rust proof prime coat with hinged front door with handle, lock & key arrangement for concealed/half concealed mounted board having knock out for conduit entry and exit for 415/230V TPN/SPN operations. The board shall have solid three phase, neutral and earth copper bus bar . MCCB/MCB's are to be so arranged as to keep the knobs projected over the inside ebonite cover. There should be provision for fixing Air-Cooler circuit breakers and emergency circuit breakers as per requirement. The work shall be complete in all respect providing necessary consumable in/c testing & commissioning, as per design, drawing and direction of Consultant / Bank Authority. Note: 1. Layout design of Distribution Board as per design must be attached inside the boards and there should be marking of all circuit breakers.		
8.1	MDB(Busbar rating of 300A) with indicator, Ameter, Volt Meter etc.	Nos	
8.2	SDB/ESDB(Busbar rating of 250A)	Nos	
8.3	DB (HAVELS - 8" x 12") for ATM	Nos	
9	PABX WORK Supplying, Fitting & fixing of following type telecommunication cable (BRB/BBS) with all necessary consumable materials in/c. testing & commissioning, as per design, drawing and direction of Consultant / Bank Authority.		
9.1	1 pair telephone cable	Rft	
9.2	2 pair telephone cable	Rft	
9.3	Telephone Socket (Legrand (Energytac)/ABB(Multiple trading)/MK (Singapore). complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Nos	
10	Supplying, fitting and fixing following boxes compatible to switches / sockets etc. made by thick galvanized steel sheet, provision for screw holding, pipe connection knock down etc. with necessary group cutting & complete in all respect as per design, drawing and direction of Consultant / Bank Authority.		

10.1	1 Gang Steel box	Nos	
10.2	2 Gang Steel box	Nos	
10.3	3 Gang Steel box	Nos	
10.4	4 Gang Steel box		
10.5	1 Gang Plastic box	Nos	
10.6	2 Gang Plastic box	Nos	
10.7	3 Gang Plastic box	Nos	
10.8	4 Gang Plastic box		
10.9	False cover	Nos	
11	BURGLAR ALARM Supply, fitting & fixing of Burglar alarm. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Nos	
12	INSECT KILLER - Brand-Khind, Model-IK-125, China	Nos	
13	ENERGY METER (Hosaf/Electro/China) Supplying and installation of following digital meter in respect providing necessary consumable in/c testing & commissioning as per design, drawing and direction of Consultant / Bank Authority.		
13.1	3 - Phase	Nos	
13.2	Single Phase	Nos	
13.3	Three Phase Digital LTCT Meter	Nos	
14	CO-AXIAL CABLE (Copper Conductor, PE Foam insulated & PVC sheathed) Supplying and installation of following RG-6 & RG-7 Co-Axial cable BRB/BBS Brand through prelaid PVC pipe/channel with all accessories as per design, drawing and direction of Consultant / Bank Authority.	Rft	
15	INDUSTRIAL EXHAUST FAN Supplying, fitting & fixing 10" & 12" dia Industrial Exhaust Fan in/c making holes in wall and mending good the damages done in/c necessary electrical connection by BRB/Paradise cables, other standard accessories/ consumables, complete in all respect in/c testing & commissioning, complete in all respect as per design, drawing and direction of Consultant / Bank Authority.		
15.1	10" (Single Phase, 0.50 KW, Metal Body)	Nos	
15.2	12" (Single Phase, 0.50 KW, Metal Body)	Nos	
16	CHANGE OVER FOR GENERATOR Change over (Local best-150A) switch for generator & Flexible cable, water grade PVC pipe etc. complete as required.	Nos	
17	AIR-CONDITIONER WATER DISPOSAL LINE Supply, fitting and fixing of 25mm & 18mm uPVC pipe with all general fitting such as bend, elbow, socket, reducing socket, Tee, unions, jam-nuts, gate valve for each air-conditioner including cutting trenches where necessary and fitting the same with earth duly rammed and fixing in walls with holder, bats and making hole in floor, walls and consequent mending good the damages etc all complete to the desired areas of usage.	Rft	
18	METAL RACEWAYS/CABLE TRAYS WITH COVER Supply fitting & fixing of Raceways of approved folded section of perforated metal sheet with approved thickness and color shall be run as suspended ceiling element and may be installed as indicated in the drawing, except that, where such raceways, etc. and being installed prior complete information regarding the final layout of all trade occupying the suspended ceiling plenum, they shall be installed in a co-ordinate Square manner so as to minimize future conflicts.		
18.1	Width 100mm X required length	Rft	
18	Width 200mm X required length	Rft	

18	<p>EARTHLING SYSTEM [If required] Supplying and installation of 120'-0" depth 1½" dia G.I. pipe earth electrode by tube well sinking method including supply of 2 SWG HDDB earthling lead from the bottom of earth electrode to the earthling bar of distribution board. Making an earth inspection pit of size 20" x 20" x 18" inside clear. Bottom of pit shall be 3" thick C.C. work and four side wall shall be 5" thick brick wall with ½" plastering and 3" thick R.C.C. cover slab. The top end of the electrode shall be 3" above from the bottom C.C. work. Complete in all respect in/c testing & commissioning, as per design, drawing and direction of Consultant / Bank Authority.</p> <p>Note: 1. Voltage between neutral and earth [Inductive voltage] must be less than 1 volt. 2. The total arrangement must be theft proof as per site condition.</p>	Set	
Sub Total			
G. DOORS, PARTITIONS, GLASS & DECORATIVE CEILING			
1.1	<p>TEMPERED GLASS DOOR Supplying, fitting and fixing imported Frameless Tempered Glass Door having 10 mm thickness with all foreign made hardware of best quality available viz. Stainless steel handleless concealed auto-closer, stopper, locking arrangement complete in all respect as per design, drawing and direction of Consultant / Bank Authority. Size : 3'- 0" W x 7'- 0"</p>	Nos	
1.2	<p>TEMPERED GLASS DOOR Supplying, fitting and fixing imported Frameless Tempered Glass Door having 10 mm thickness with all foreign made hardware of best quality available viz. Stainless steel handleless concealed auto-closer, stopper, locking arrangement complete in all respect as per design, drawing and direction of Consultant / Bank Authority. Size : 3'- 0" W x 8'- 0"</p>	Nos	
2.1	<p>TEMPERED GLASS DOOR (Main Entry) Supplying, fitting and fixing imported Frameless Tempered Glass Door having 10 mm thickness with all foreign made hardware of best quality available viz. Stainless steel handleless concealed auto-closer, stopper, locking arrangement complete in all respect as per design, drawing and direction of Consultant / Bank Authority. Size : 2'-6" W X 7'-0"</p>	Nos	
2.2	<p>TEMPERED GLASS DOOR (Main Entry) Supplying, fitting and fixing imported Frameless Tempered Glass Door having 10 mm thickness with all foreign made hardware of best quality available viz. Stainless steel handleless concealed auto-closer, stopper, locking arrangement complete in all respect as per design, drawing and direction of Consultant / Bank Authority. Size : 2'-6" W X 8'-0"</p>	Nos	
3	<p>FRAMELESS 10mm GLASS PARTITION Supplying, fitting and fixing 10 mm thick clear float glass partition, upper and lower sides are fixed with 1" aluminum U-Channel section, complete in all respect as per design, drawing and direction of Consultant / Bank Authority.</p>	Sft	
4	<p>ALUMINUM SLIDING PARTITIONS (Fixed) Supplying, fitting and fixing of aluminum sliding windows/doors of 3" silver colored anodized aluminum section with all foreign made hardware of best quality available viz: handle, locks, wheels original bronze anodized star head matching screws, weather seal/ Mohair, rubber gasket, rivets, neoprene, sealant etc. in/c fitting and fixing of distortion free 6 mm thick clear float glass of approved quality and shade of foreign origin in/c fixing all necessary accessories etc. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.</p>	Sft	

5	ALUMINUM SLIDING DOOR Supplying, fitting and fixing of aluminum sliding windows/doors of 3" silver colored anodized aluminum section with all foreign made hardware of best quality available viz: handle, locks, wheels original bronze anodized star head matching screws, weather seal/ Mohair, rubber gasket, rivets, neoprene, sealant etc. in/c fitting and fixing of distortion free 5 mm thick clear float glass of approved quality and shade of foreign origin in/c fixing all necessary accessories etc. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Sft	
6	ALUMINUM SLIDING WINDOW Supplying, fitting and fixing of aluminum sliding windows/doors of 3" silver colored anodized aluminum section (Brand-KAI) with all foreign made hardware of best quality available viz: handle, locks, wheels original bronze anodized star head matching screws, weather seal/ Mohair, rubber gasket, rivets, neoprene, sealant etc. in/c fitting and fixing of distortion free 5 mm thick clear float glass of approved quality and shade of foreign origin in/c fixing all necessary accessories etc. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Sft	
7	ALUMINUM LOUVER Supplying, fitting and fixing of aluminum louver screen to house outdoor AC units made of 4" section colored anodized / powder coated aluminum louver sections with all foreign made hardwires, sealant etc. in/c required scaffoldings etc. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Sft	
8	WOODEN LOUVER Supply, fitting and fixing of wooden louver with 18mm thick gorjan ply @ 75mm c/c vertical distance, 75mmX50mm gorjan wood @ equal distance to horizontal suspended from ceiling as per design including, nails, screw, rowel plugs, rowel bolts, polish, cutting, sizing etc. all complete as per design, direction and full satisfaction of the Bank authority.	rft	
9	CURTAIN GLASS WORK Supply, fitting & fixing of glass partition in front elevation made of 6 mm approved reflected color glass with by 80mmx80mm aluminum curtain glass section all aluminum members will be anodized silver section (KAI, Fuwang) including all accessories like black color silicon gum, reopen sealant, screws, rowel plug, rowel bolt, nails, scaffolding etc. all complete as per Bank standard and full satisfaction of the Consultant / Bank Authority.	Sft	
10	ENGRAVED GYPSUM BOARD CEILING Supplying, fitting and fixing 10 mm thick approved quality Gypsum board false ceiling fixed over powder coated T-bar & cross T of section 1"X 1½", and L-angle of section 1" X 1" at edges, at 2'-0" X 2'-0" grid suspended from ceiling by 12 SWG double ply G.I. wire fixed to the ceiling by rowel plug, iron angles, screws, hooks, nails etc. maintaining straight lines and desired finished level at bottom face with vertical wooden strut as required in/c making holes in slabs, or beams by electric drill machine and mending good the damages, if any, during execution of the work in/c cost of all materials, accessories, scaffoldings, labor for installation, screws, nails, etc. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Sft	
11	GROOVE MINERAL BOARD CEILING Supply, fitting & fixing of 600mm X600mm X 15 mm grove mineral board (China) false ceiling over powder coated T-bar of section 25mmx38mm and L-angle of section 25mmx25mm at edges, at 600mmx600mm grid suspended ceiling by rowel plug iron angles 12 SWG G.I. wire, screws, hooks, nails etc. maintaining straight lines and desired finished level at bottom face with vertical or beams by electric drill machine damage if any during the materials, accessories, scaffolding, labor for Installation etc. all complete as per Bank standard and full satisfaction of the Consultant / Bank Authority.	Sft	

12	<p>METAL BOARD CEILING Supplying, fitting and fixing 0.7 mm thick approved quality Metal board false ceiling fixed over powder coated T-bar & cross T of section 1"X 1½", and L-angle of section 1" X 1" at edges, at 2'-0" X 2'-0" grid suspended from ceiling by 12 SWG double ply G.I. wire fixed to the ceiling by rowel plug, iron angles, screws, hooks, nails etc. maintaining straight lines and desired finished level at bottom face with vertical wooden strut as required in/c making holes in slabs, or beams by electric drill machine and mending good the damages, if any, during execution of the work in/c cost of all materials, accessories, scaffoldings, labor for installation, screws, nails, etc. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.</p>	Sft	
13	<p>PVC BOARD CEILING AT TOILET AREA Supply, fitting and fixing of 12mm hollow type PVC board [2'-0"X2'-0"] false ceiling of approved quality in toilet/kitchen area over powder coated T-bar of section 1" X 1.5" and L-angle of section 1" X 1" at edges, at 2'-0" X 2'-0" grid suspended ceiling by rowel plug, iron angles, 12 SWG G.I. wire, screws, hooks, nails etc. maintaining straight lines and desired finished level at bottom face with vertical or beams by electric drill machine and mending damage if any during the materials, accessories, scaffolding, labour for installation etc. All complete as per design direction and full satisfaction of Consultant / Bank Authority.</p>	Sft	
14	<p>PLAIN GYPSUM / PARTEX BOARD DESIGN FIXED CEILING Supplying, fitting and fixing false ceiling and paneling of ½" thick plain Gypsum board/Plain PARTEX board having maximum compressive pressure, suspended from existing R.C.C. ceiling of the building at a level of 8'-0" [or as per direction] height on a 2'-0" x 2'-0" grid frame work of C steel section/1½" x 2½" wooden section of best quality seasoned Garjan wood in/c anchoring the alternate junctions with 12 SWG double ply G.I. wire fixed to the ceiling by rowel plug, screws, hooks, nails etc. maintaining straight lines and desired finished level at bottom face with vertical wooden strut a required in/c making holes in slabs, or beams by electric drill machine & mending good the damages if any, during execution of the work in/c cost of all materials, accessories, scaffoldings, labour for installation, screws, nails, etc, making provisions for lighting arrangement, including painting with at least 3 coats of approved colour plastic paint over a coat of priming in/c necessary sanding, putty works etc. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.</p>	Sft	
15	<p>LOUVER TYPE CEILING (MELAMINE BOARD) : Supply, fitting & fixing of Louver type Ceiling 6"x1" @ 6" C/C made of 25 mm thick melamine board Star particle or Amber Brand Graphite color hung with M.S Furring Channel at desired level with necessary hardware etc. all complete as per existing samples, design drawings, direction and full satisfaction of the Architect/Bank Authority.</p>		
16	<p>ALUMINIUM / METAL BOX FRAME CEILING (1.75"x1.75") : Supply, fitting & fixing of Aluminum square box frame (1.75"x1.75") on Ceiling horizontally & vertically at desired level wall to wall with</p>		
17	<p>WOODEN DROP for Fixed Glass & Door: Supply, fitting & fixing of plain wooden drop over the glass partition suspended from existing R.C.C. slab of the building at the level of 2550mm (or as per direction) height made of 12mm thick white partex over frame of section 75mmX38mm at 600X600mm in grid suspended from ceiling or roof with 50mmx25mm best quality seasoned Garjon wood section, 75mm screw, nails, rowel plug, fevicol aica and 03(Three) coats of plastic paint over primer coat, putty, racking out joints etc. including AC side covering. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.</p>	Rft	

18.1	COLUMN/WALL CLADDING Supply, fitting & fixing of Full/Low Height column or Wall cladding made of 1/2" partex board laminated (Star partex) with Approved color, cladded on tilted wooden frame and 1" Stainless Steel bit 2' center to center horizontally etc. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Sft	
18.2	COLUMN/WALL CLADDING Supply, fitting & fixing of Full/Low Height column or Wall cladding work with aluminum composite panel (Tiger /Alco best / Approved brand) of approved quality [4mm thickness,] cladded with extra ordinary fine finish on standard and necessary aluminum box section framing etc complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Sft	
18.3	COLUMN/WALL CLADDING Supplying, fitting & fixing of wall cladding made of 2"x1" garjon wooden frame @2'X2' grid line, frame Venner board, and other accessories etc. Also have provision for Light Guarder. All complete as per design direction and full satisfaction of the Consultant / Bank Authority.	Sft	
18.4	GLASS & VENEER BOARD PANELING (MAIN ENTRY) Supplying, fitting and fixing of 10mm glass (clear) polished edge on aluminium "U" section with gasket, ss screws shall have to meet the material strength and properties as specified above and meet the relevant European (EN) and American (ASTM) standards applicable to the mentioned Glazed Partition System. All complete as per design direction and full satisfaction of the Consultant / Bank Authority.	Sft	
18.6	DESIGN FEBRIC CLADDING Supply, fitting and fixing of fabric cladding work over wooden paneling, glued on the ply clad with imported fabric (China/ Korea) of approved quality and color, fixed at wall, including iron mongeries and all necessary hardware all hand tools and other necessary consumables etc. All complete as per design direction and full satisfaction of Consultant / Bank Authority.	Sft	
19	CASH BACK WALL DESIGN PANELLING WORK Supply , fitting & fixing of Cash back wall design cladding work made of 2"x1" gorjon wooden frame, 2'x2'Grid line over pasted particle board, have provision for light guarder, paint finish and other standard hardware etc. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Sft	
20.1	PARTEX FLUSH DOOR Supplying, fitting and fixing 1½" thick Garjan/Commercial Veneered 'PARTEX' Flush door in/c supplying and making of door frames of best quality and well seasoned Ctg. Shill Karai/Garjan of section 6" X 2" [5" wall flush] in/c painting two coats of Coaltar/Enamel paint to the surface in contract with wall, lock & other accessory fitted and fixed in position by 6 nos. heavy type iron clamps and mending good the damages if any in/c fitting and fixing best quality 4 nos. 4" antique color iron hinges, 2 nos. best quality 6" aluminum tower & socket bolts [BTA], Alpha-Japan or equivalent mortise door lock, in/c applying 3 coats of approved color enamel paint of Berger brand over a coat of priming in/c cleaning, finishing and polishing with sand paper, putty works etc. complete in all respect as per design drawing and direction of Consultant / Bank Authority. [Door Size : 3'-0" x 7'-0"]	Nos	

20.2	<p>PARTEX FLUSH DOOR Supplying, fitting and fixing 1½" thick Garjan/Commercial Veneered 'PARTEX' Flush door in/c supplying and making of door frames of best quality and well seasoned Ctg. Shill Karai/Garjan of section 6" X 2" [5" wall flush] in/c painting two coats of Coaltar/Enamel paint to the surface in contract with wall, lock & other accessory fitted and fixed in position by 6 nos. heavy type iron clamps and mending good the damages if any in/c fitting and fixing best quality 4 nos. 4" antique color iron hinges, 2 nos. best quality 6" aluminum tower & socket bolts [BTA], Alpha-Japan or equivalent mortise door lock, in/c applying 3 coats of approved color enamel paint of Berger brand over a coat of priming in/c cleaning, finishing and polishing with sand paper, putty works etc. complete in all respect as per design drawing and direction of Consultant / Bank Authority.</p> <p>[Door Size : 2'-6" x 7'-0"]</p>	Nos	
21	<p>PVC DOOR Supplying, fitting and fixing 'RFL/Partex Bengal' brand PVC door of approved type in/c all fittings viz. Bolts, hinges, best quality mortise door lock etc. complete in all respect as per design, drawing and direction of Consultant / Bank Authority. [A] Door Size : 2'-6" x 7'-0"</p>	Nos	
22	<p>ALUMINUM SWING DOOR (Brand- KAI) with 5mm clear glass, door closer grade 1 (Thailand), Door lock (Imported), door glass bit, door handle, door divider, neoprene, rivet (Taiwan), wood screw, connecting rod, nut bolt etc complete in all respect as per design, drawing and direction of Consultant / Bank Authority.</p>	Nos	
23	<p>SINGLE LEAF METAL FIRE RATED DOOR (UL Certified) Supply & installation of approved make 40mm thick light weight asbestos free fire proof doors (NFPA 80, ANSI/UL 10 B & ANSI/UL 10 C Standard) complete in all respect as per details Pre-lacquered finish. Door Frame: Made by high quality imported Cold Rolled Mild Steel sheet, 2.3mm thick Geometrical profile as per UL outline subject 63, Single Rabbet and Double Rabbet. Throt opening is 140mm. Size 140mm x 80mm. Leaf: Made by high quality imported cold Rolled Mild steel sheet, Thick 1.6mm Leaf width is 50mm face sheet and bottom sheets assembled with interlocking mechanism and MIG TAC welded. Accessories: Door Hinges: 4.5" X 4" X 3.4mm Stainless Steel door hinges, fire rating 180 minute, high security door locks meeting grade-1, ANSI A 156.13 Latch bolt: 3/4" (149mm) Throw, Stainless steel, fire rating 3.0 hours, Panic Bar: Touch bar with smooth operation RIM type or Vertical Rod type UL Listed / ANSI grade-1 with Silver coated paint finish. Vision Panel: Maximum glazed area 100 in2 180 minutes fire rating, Positive Pressure Tested. Complete in all respect as per design, drawing and direction of Architect/Authority.</p>	Nos	
24	<p>DOOR LOCK Supply, fitting & fixing of round cylinder type Imported door lock in position of best quality silver color including all required accessories ensuring minimum injury to door shutter and frame etc. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.</p>	Nos	
25	<p>WOODEN DOOR CLOSER Supply, fitting & fixing of imported door closer of approved quality in position including all required accessories ensuring minimum injury to door shutter and frame etc. Complete in all respect as per design, drawing and direction of Consultant / Bank Authority.</p>	Sft	
26	<p>SOLID PARTITION Supplying, fitting and fixing false ceiling and paneling of ½" thick plain Gypsum board/Plain PARTEX board having maximum compressive pressure at 600X600mm in grid suspended from ceiling, roof, floor, RCC and wall or beam by rowel plug & 75mm screw, nail etc with 03 coat of paint all complete as per Bank standard and full satisfaction of the Consultant / Bank Authority.</p>		

	a) Partition with both side Board	Sft	
	b) Partition with one side Board	Sft	
27	MDF PLY PASTING Supplying & pasting of MDF (2.5/3 mm thick) sheets upon partitions with glue, making the surface absolutely smooth and bubble free. All complete as per design, direction and full satisfaction of the Consultant / Bank Authority.	Sft	
28	DESIGN DRY PARTITION Supplying, fitting & fixing of partition (3" thick) made of veneer board/MDF board, gorjan wooden framing decorative sheet edge works including French polishing 3 coats, provision for Light Guarder etc. All complete as per design direction and full satisfaction of the Consultant / Bank Authority.	Sft	
29	DESIGN WOODEN LOUVER POST (4"x2") Supply, fitting & fixing of 100x75mm Wooden louver post made of 3"x2" garjon solid wooden frame over 1/2" veneer board with mat vernish including. All complete as per design, direction and full satisfaction of the Consultant / Bank Authority.	Rft	
30	50MM LOW HEIGHT FABRIC PARTITIONS FOR WORKSTATIONS: 2" Aluminum Profile partition (Brand-KAI) with two wire trunking with poly carbon /6mm clear glass or with fabric/leather or artificial resin with 3mm glass all complete as per design and direction including all accessories to fixing the top like cantilever, L Clamp, Screw etc complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Sft	
31	32MM LOW HEIGHT FABRIC PARTITIONS FOR WORKSTATIONS : Aluminum Profile partition (Brand-KAI) with wire trunking with poly carbon /6mm clear glass or with fabric/leather or artificial resin with 3mm glass all complete as per design and direction including all accessories to fixing the top like cantilever, L Clamp, Screw etc complete in all respect as per design, drawing and direction of Consultant / Bank Authority.		
32	25MM LOW HEIGHT FABRIC PARTITIONS FOR WORKSTATIONS: 1" Aluminum Profile partition (Brand-KAI) with wire trunking with poly carbon /6mm clear glass or with fabric/leather or artificial resin with 3mm glass all complete as per design and direction including all accessories to fixing the top like cantilever, L Clamp, Screw etc complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Sft	
Sub Total			
H. MISCELLANEOUS WORKS			
1	VENETIAN BLIND [ROLLER] Supply, fitting & fixing of imported best quality blinds of approved color with all imported accessories say pvc coupling cod controlling chain, bottom weight plate, bottom chain etc. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Sft	
2	VENETIAN BLIND [VERTICAL] Supplying, fitting and fixing in position imported best quality 125 mm wide vertical blinds of approved color and quality with all imported accessories complete in all respect as per design, drawing & direction of Consultant / Bank Authority.	Sft	
3	PRAYER CARPET Supply fitting fixing of Roll carpet for prayer room, including all necessary hardware materials. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Sft	
4	ROLL CARPET Supply fitting fixing of Roll carpet for prayer room, including all necessary hardware materials. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Sft	

5	CARPET WORK (CARPET TILES) Supplying & fitting-fixing of imported 8mm pile height PVC plus Glass fibre backed 100% BCF solution dyed looped pile Synthetic Carpet fixing with glue, 100% solution dyed nylon pile height +/- 3.5mm. Face weight 20oz/sq.yd, (with compliance to Flammability, Dimensional Stability, Colorfastness to Light & Electrostatic Propensity standards). complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Sft	
6	SELF ADHESIVE FROSTED PAPER Supplying, fitting and fixing frosted paper on Main entry door and other glass surfaces after cutting logo and lettering with fine finish, complete in all respect as per design, drawing & direction of Consultant / Bank Authority.	Sft	
7	PVC BOARD (3mm thick) Supply, fitting and fixing of 3mm pvc board (Brand: Partex/Amber/Bengal) screw, steel nails, adhesive, putting including best quality of hardware materials etc. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Sft	
8	PVC BOARD (5mm thick) Supply, fitting and fixing of 5mm pvc board (Brand: Partex/Amber/Bengal) screw, steel nails, adhesive, putting including best quality of hardware materials etc. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Sft	
9	WALL PAPER Supply, fitting and fixing of 525mm/ 700mm width wall paper (China) approved color and quality to be fixed in the designated walls of approved color including adhesive, labor, pasting, cutting etc. complete in all respect as per design, drawing & direction of Consultant / Bank Authority.	Sft	
10	TOILET & DINING SIGNAGE Supplying and fitted of toilet signage including all necessary standard tools and hardware. all respect as per design, drawing & direction of Consultant / Bank Authority.	Nos	
11	PEDAL BIN (WASTE PAPER BOX) Supply, fitting & fixing of Pedal Bin (Dia 12") made of high quality Black colored perforated screen. all respect as per design, drawing & direction of Consultant / Bank Authority.	Nos	
12	PVC DOOR MAT Supplying, fitting and fixing best quality imported PVC mat [Dust catcher] complete in all respect as per direction of Consultant / Bank Authority.	Sft	
I. FURNITURE WORKS			
1	TELLER & BILLING COUNTER (R.C.C STRUACTION WITH MARBLE) Supply, making, fitting & fixing of Teller counter made of indian marble cladding over 10" brick work with 3" R.C.C slab on the top marble stand partition with 10mm thick glass at top of the counter fitted with S.S metal post, & front side 10mm glass, bottom t-5 light arrangement. Also having melamine coated board work top with (0-nos) mobile drawer unite & (0- nos) key board for each etc. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Rft	
1.1	TELLER & BILLING COUNTER (WOODEN STRUACTION WITH MELAMINE BOARD & MARBLE) (Same as Corporate Branch) Supply, making, fitting & fixing of Teller counter made of Melamine board (Approved colour), indian marble cladding (Approved colour), including 10mm navy blue sticker (Bank's Brand color) pasted glass with 10mm thick glass at top of the counter fitted with S.S metal post, & front side 10mm glass, bottom t-5 light arrangement also having melamine laminated board (Approved colour) work top with & key board for each etc. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Rft	

7	LOW HEIGHT/OVER HEAD CABINET Supply, fitting & fixing of low height cabinet made of 3/4" Partex board (Approved Colour) and best quality hardware materials etc. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Sft	
8	FULL HEIGHT CABINET Supply, fitting & fixing of full height cabinet made of 3/4" Partex board (Approved Colour) and best quality hardware materials etc. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Sft	
9	SDB BOARD CABINET Supply, fitting & fixing of full height cabinet made of 3/4" Partex board (Approved Colour) and best quality hardware materials etc. complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Sft	
10	CHEQUE WRITING TABLE : Supply, fitting & fixing of table made of Stainless steel framing and 8 mm bubble glass top complete in all respect as per design, drawing and direction of Consultant / Bank Authority.	Nos	
17	KITCHEN & WASH UNDER SHUTTER Supply, fitting & fixing of Kitchen & wash under shutter made of 3/4" PVC Board including other standard hardwares etc. All complete as per design direction and full satisfaction of consulting consultant.	Sft	
18	TV CABINET FOR LOUNGE AREA Supply fitting fixing of design TV cabinet for lounge area made of 12mm thickness veneer board gorjon wooden framing best quality hard ware, approve colour polish finish etc. All complete as per design, direction and full satisfaction of consulting consultant.	Sft	
Common Maintenance Works			
1	Labour bill per day per person	Nos	
2	Masson bill per day per person	Nos	
3	Conveyance /Service charge for complain attend (In Side Dhaka/City)	Nos	
4	Conveyance/service charge for complain attend (outside Dhaka/city)	Nos	
5	9 watt LED Bulb	Nos	
6	12 watt LED Bulb	Nos	
7	18 watt LED Bulb	Nos	
8	20 watt LED Bulb	Nos	
9	LED Panel Light 6 Watt	Nos	
10	LED Panel Light 9 Watt	Nos	
11	LED Panel Light 12 Watt	Nos	
12	LED Panel Light 18 Watt	Nos	
13	LED Panel Light 20 Watt	Nos	
14	LED Panel Light 24 Watt	Nos	
15	Rechargeable light 18/20 watt	Nos	
16	Energy Light (24 Watt)	Nos	
17	LED Panel light 4'X6"	Nos	
18	LED Panel light 1'X1'	Nos	
19	LED Panel light 2'X2'	Nos	
20	2 PIN Socket	Nos	
21	3 Pin Socket	Nos	
22	6 Pin Socket	Nos	
23	Cable Tie 4"	pkt	
24	Cable Tie 6"	pkt	
25	Cable Tie 8"	pkt	
26	Cable Tie 10"	pkt	

27	Premises wiring check	Job	
28	Electric power port repairing	Nos	
29	Power Cable (Oven & Kettle) (10 A, 15A, 20A)	Nos	
30	LED switch for paper shredder machine	Nos	
31	Micro oven Moving Tary	Nos	
32	Micro oven Motor	Nos	
33	Micro Oven Repairing	Nos	
34	Kettle Coil replace	Nos	
35	Kettle repairing	Nos	
36	New power port with all accessories	Nos	
37	TV Remote	Nos	
38	AC Remote	Nos	
39	Solar Inverter (different rating)	Nos	
40	Solar Charge Controller	Nos	
41	Solar Battery Cable	Rft	
42	Tempered Door Repairing	Nos	
43	Tempered Door Lock Repairing	Nos	
44	Tempered Door Handle	Nos	
45	Tempered Door Closer	Nos	
46	Tempered Door Lock	Nos	
47	Glass Door Bottom/Top	Nos	
48	Drawer Channel	Nos	
49	Drawer Lock	Nos	
50	Drawer Center Lock	Nos	
51	Hole Cap SS	Nos	
52	Hole cap Plastic	Nos	
53	Wooden cabinet /drawer unit repairing with accessories	Nos	
54	Wooden cabinet /drawer unit repairing with board	Nos	
55	Desk repairing wth accessories	Nos	
56	Desk repairing without accessories	Nos	
57	Steel Cabinet lock replae	Nos	
58	Steel Cabinet repairing	Nos	
59	Round door lock (wooden)	Nos	
60	Vertical blind stand/upper hanger/channel	Rft	
61	Roller blind stand/upper hanger/channel	Rft	
62	Vertical blind repairing with components	Sft	
63	Vertical blind repairing without components	Sft	
64	Plastic Tin shed with Angle& Accessories	Sft	
65	Profile Tin shed with Angle& Accessories	Sft	
66	Tin shed Angle& Accessories	Sft	
67	Auto Air Freshener with refill & Battery	Nos	
68	Old Tiles dismantling & cleaning	Sft	
69	Wall Damp Treatment/remove	Sft	
70	Collapsible Gate/Gate repairing with accessories	Sft	
71	Collapsible Gate /gate repairing without accessories	Sft	
72	Shutter Spring bati	nos	
73	Wash room jam clear	Job	
74	Kitchen Cup Hanger	Job	

75	Basin west	Nos	
76	Sink West	Nos	
77	Lowdown Fittings	Nos	

A. General Terms and Conditions:

1. **Financial Offer/Price/Quotation:** The quoted price should include applicable VAT. The rate of VAT should be mentioned in the quotation.
2. **Work Location/Delivery Place:** Community Bank Bangladesh Limited Head Office along with Branches, ATM Booth and other Bank Location.
3. **Payment Terms:** Payment will be made after each completion the job at actual quantity upon submission of the bill with work order & noc from the deployed location which is duly signed by authorized personnel (Name & Seal, if available). Payment will be made through the Bank Account only.
4. **Price/Financial offer Submission:** The bidder shall have to submit the price in the letter head pad.
5. The Bidder shall have to submit their proposal following the above information.
6. **Purchaser's Right:** The Purchaser reserves the right to accept/ cancel/ reject any or all offer without assigning any reason. The purchaser is not obliged to purchase the lowest offer at all. The purchaser reserves the right to share the Bidder's response to this RFQ with its advisors and purchaser Business Units. Purchaser reserves the right to conduct negotiations with one or more Bidder and / or accept the Bid without any negotiations.
7. **Bid Submission/ Closing Date:** The Quotation shall have to the submit below mentioned address: **Chairman Purchase Committee**, General Services Division 12th Floor, Community Bank Bangladesh Limited, Police Plaza Concord, Tower-2, Road-144, Plot-02, Gulshan-01, Dhaka by 12.00 PM (Bangladesh Standard Time) December 07, 2022. The purchaser reserves the right change the Time schedule at any time.
8. **Required Content of the Quotation:** Quotation must be submitted as per prescribed form as instructed below:
 - A. Proposal must be addressed for "**Chairman purchase Committee**" of Community Bank Bangladesh Limited.
 - B. Complete Proposal / Offer must be signed with date by the authorized representative of the company.
 - C. Must mention the subject line "**Tender and Enlistment for Interior Decoration & Electrical Repair Maintenance Works for Community Bank Bangladesh Limited. (Ref: CBBL/GSD/RFQ/2022/0042)**" in top of the Envelope.
9. **Quotation Validity:** The Quotation shall be valid for 365 calendar days (01 Year) from the Quotation submission/ closing date. Which will continue for a year/until further notice (if both parties agreed). Details discussion/terms & condition will be available in Service Level Agreement (SLA).
10. **Disqualification:** Manipulation or any kind of unusual approach or failure to submit the proposal/ offer within stipulated time frame will be treated as "Disqualification" to attend in the bidding.
11. **Sample/Test of the Product/Service:** Bank may ask mock test before selection of any vendors which is FOC (Free of Cost).

B. Financial Terms & Conditions:

12. Quoted Price must include material, labor and service charges as per attached price format.
13. Delivery lead-time will be as per site and Bank requirements.

14. In the event of supply of any items, which do not match with the required specification, quantity or sample's quality or is of substandard quality, the Bank reserves the right for outright rejection of the works/product, and the supplier will have to do the works/supply the product again with their own cost with acceptable quality within 30 (thirty) days from the date of rejection.
15. Detail Technical Specifications along with country of origin must be mentioned in the offer and all the relevant documents including Catalog and Brochures must be attached with offer. If the Tenderer is an authorized dealer/distributor of the said product they will provide the document of dealership/distributorship of the Manufacturer.
16. Following papers/documents must be sent with the proposal:
 - I. Valid Trade License
 - II. Bank solvency certificate/documents (If applicable)
 - III. VAT Registration certificate
 - IV. Up-to-date TIN certificate
 - V. Up-to-date copy of TAX payment receipt
 - VI. Client list with goodwill certificate (If available)
 - VII. Experience certificate (If available)
17. Mode of Payment is to be mentioned in the offer. Community Bank Bangladesh Limited discourages advance payment if not necessary.
18. Please contact undersigned for any types of clarifications in regard to products/services/works related clarifications only.

Thanks & Best Regards

S.M. Shahin Iqbal
SAVP & Head of General Services Division (GSD)
Head Office
Community Bank Bangladesh Limited.