**Date- November 05, 2026**

**Tender Reference# CBBL/GSD/RFQ/2026/0089**

**Tender Title-** **RFQ (*Request for Quotation) for VRF AC new Indoor Unit Supply, installation with dismantle and re-fitting works***

Dear Sir,

Quotation (BOQ with Technical Assessment Sheet attached herewith) is hereby invited rate *for*

***i) VRF AC new Indoor Unit Supply, installation with dismantle and re-fitting works***

*at Community Bank Bangladesh PLC.*

You are requested to submit **(HARD COPY)** your offer in a closed envelope as per below specification **within 12.00 P.M. on November 11, 2026 addressing "Chairman, Purchase Committee, Community Bank Bangladesh PLC. (Tender Reference# CBBL/GSD/RFQ/2026/0089)**

- ✓ **No advance will be allowed in this regard.**
- ✓ **All price/ rate should be inclusive of Carrying Charge, Installation Cost and related Materials, VAT and Tax which will be deducted from source during payment of final bill after satisfactory completion of the works.**
- ✓ **Retention money will be kept i.e. 10% of the total payable bill of new supply will be kept for 01 (one) year (in case, total work order value is above BDT 50,000.00)**

**Other terms, conditions and mode of payment will be as under:**

*a)* Ready stock will be given preference.

*b)* All work must follow standard safety practices, especially during gas handling, welding, and equipment relocation.

*c)* All gas, fittings, and welding materials must be of original and approved quality, compatible with existing VRF AC specifications.

*d)* Final handover will occur only after successful system testing, pressure checks, and commissioning to client satisfaction.

*e)* Gas charging and indoor unit relocation will be executed based on actual requirements, subject to on-site verification and approval by the Bank's authorized personnel."

*f)* Delivery Challan duly received by Concerned Division is to be submitted along with the bill.

*g)* Date of delivery or completion of work will be counted from the date of Work Order received/ acknowledged either by signing the Office Copy of Work Order or by e-mail confirmation whichever is earlier.

*h)* In the event of supply, Installation and commissioning of the work, if the said items/services does not match with as per requirement/approved quotation then, the Bank reserves full right of outright rejection of the items, and the supplier will have to take back the supplied items at their own cost and will have to replace the said items with acceptable within the time frame as mutually agreed-upon by the Bank and the Supplier.

*i)* The product must be supplied as per specification mentioned in quotation. If any change, Supplier will have to consult with the General Services Division, Head Office of the Bank.

*j)* In case of deviation from the quality and specification and/or delay in supply, bank preserves full right to reject the materials and cancel the work order without showing any reason.

*k)* In case of any deficiency in the delivered product, supplier will have to make necessary rectification the same immediately at Supplier own cost on receipt of complain.

*l)* No additional bill/work will be entertained without prior permission of General Services Division.

*m)* Financial offer should be valid for Minimum 06 (six) months

Community Bank Bangladesh PLC. GSD, Head Office, Dhaka

n) Price quotation includes carrying cost, labor charge, Supply, installation, commissioning and other charge thereof.

o) The bank will carry out a detailed evaluation of the quotation according to the information supplied by the bidder through its proposal.

p) Considering the Experience, quality and other factors, CBBL is not liable to select the lowest bidder.

q) The bank reserves the right to accept or reject any or all quotation at any time prior to award of contract, without thereby incurring any liability to the affected bidder or bidders or any obligation to inform the affected bidder or bidders of the grounds for the Bank's action.

r) Selected Bidder must ensure to site Installation & Testing on site after sales support for the full warranty period

s) For any type of sub-standard quality product from selected bidder end, the Bank reserve the right for outright rejection of the goods, which you will take back at bidder own cost and will replace with acceptable quality within (10) ten days of the rejection.

t) The work is required to be carried out during non-business hours; in case of business hour work supplier ensure no disturbance is caused to nearby premises and should take prior approval.

***The new bidders must submit the following Paper:***

1. Company Profile
2. Trade License
3. TIN, Bin Copy
4. Bank Solvency Certificate
5. Recent Work order/ Performance Certificate
6. Other relevant documents.

**Payment:**

- Bill should be submitted along with Work Order and Delivery Challan and performance certificate signed by the Branch Authority.
- Price includes delivery, installation including all installation materials and commissioning charges.
- All Price should be including all VAT and TAX. Necessary VAT & Tax will be deducted from your bill as per latest Govt. circular.
- Payment will be made after submission the bill only through account transfer.

***Vendors whose scope of works does not match with the said job need not to submit their offer.***

**Regards,**

Md. Zahid Ibne Anwar
Head of General Services Division
**Community Bank Bangladesh PLC.**

Community Bank Bangladesh PLC. GSD, Head Office, Dhaka

## BILL OF QUANTITY SCHEDULE FOR AIR CONDITIONING SYSTEM

### VRF AC new Indoor Unit Supply, installation with dismantle and re-fitting works

### Schedule: A- Supply of Imported Items (VRF)

### Brand: DAIKIN Total Cooling Load -IDU: 6TR

| Sl. No. | Description (Imported Items) | Model Number | Qty. | Unit | Unit Rate (BDT) | Total Amount (BDT) |
|---|---|---|---|---|---|---|
| 1.0 | **VRV Fan Coil Unit (Indoor Unit)** | | | | | |
| | Fan coil units having cooling capacities as mentioned below. Each unit shall be operated with Variable refrigerant Flow (VRF/VRV) outdoor units. FCU shall have refrigrant control valve (EXV) washable filter, fan speed controller etc. complete in all respect. Vent port shall be built in inside unit. The unit shall operate when supplied with 210-230 v/50 hz/1 ph Electric power. | | | | | |
| | **Brand: DAIKIN**<br>**Origin: JAPAN**<br>**ASSEMBLE: INDIA** | | | | | |
| 1.1 | Capacity: 3.6 KW (1.5TR) | FXFSQ50ARV1 | 4 | Sets | | |
| 1.2 | Panel | BYCQ125EAF6 | 4 | Sets | | |
| 1.3 | Wireless Sensor | BRC7M632F-6 | 4 | Sets | | |
| 1.4 | Wireless Remote Controller | BRC4M150W16 | 4 | Sets | | |
| 1.5 | Refnet Joint. | KHRP26A33T6 | 3 | Sets | | |
| | | | | | **Total Price Including Vat & Tax** | - |

Community Bank Bangladesh PLC
GSD, Head Office, Dhaka

## BILL OF QUANTITY SCHEDULE FOR AIR CONDITIONING SYSTEM

### VRF AC new Indoor Unit Supply, installation with dismantle and re-fitting works

### Schedule: B- Supply, Installation & Labor Cost of All Imported & locally sourced Items

| S/N | Description | Qty. | Unit | Material Cost per Unit (BDT) | Labor Cost per Unit (BDT) | Total Amount (BDT) |
|---|---|---|---|---|---|---|
| **1.0** | **Installation of Imported Items** | | | | | |
| 1.1 | Indoor Unit Installation | 6 | sets | | | |
| 1.2 | Indoor Unit Dismantle | 3 | sets | | | |
| 1.3 | Refnet Joint | 3 | sets | | | |
| **2.0** | **Local Items** | | | | | |
| | **REFRIGERANT COPPER PIPE FOR VRF SYSTEM PIPING** | | | | | |
| | **Brand:** Haike/Jintian/Muller/Coppertech | | | | | |
| | **Origin:** China/Bangladesh | | | | | |
| | | | | | | |
| **2.1** | **Coil Pipe (For IDUs Only):** | | | | | |
| 2.1.1 | 6.4mm or 1/4" dia, Thickness: 0.38 mm | 100 | Rft | | | |
| 2.1.2 | 9.5mm or 3/8" dia, Thickness: 0.42 mm | 50 | Rft | | | |
| 2.1.3 | 12.7mm or 1/2" dia, Thickness: 0.51 mm | 100 | Rft | | | |
| 2.1.4 | 15.9mm or 5/8" dia, Thickness: 0.59 mm | 50 | Rft | | | |
| | | | | | | |
| | **Straight Pipe:** | | | | | |
| 2.1.5 | 9.5mm or 3/8" dia, Thickness: 0.80 mm | 38 | Rft | | | |
| 2.1.6 | 15.9mm or 5/8" dia, Thickness: 0.80 mm | 38 | Rft | | | |
| | | | | | | |
| **3.0** | **Refrigerant piping insulation For VRF System** | | | | | |
| | Nitrile Rubber Insulation<br>Thickness of insulation 19mm | | | | | |
| | **Insulation Brand :**<br>Armacell/Superlon/Allflex/Copperlon/Insulflex/Armaflex/Aflex<br>**Origin:** Malaysia/India | | | | | |
| | | | | | | |
| 3.1 | 6.4mm or 1/4" dia Thickness 19mm | 100 | Rft | | | |
| 3.2 | 9.5mm or 3/8" dia Thickness 13mm | 88 | Rft | | | |
| 3.3 | 12.7mm or 1/2" dia Thickness 19mm | 100 | Rft | | | |
| 3.4 | 15.9mm or 5/8" dia Thickness 19mm | 88 | Rft | | | |
| | | | | | | |
| **4.0** | **Condensate drain piping for VRF System** | | | | | |
| | Supply of SWR Grade uPVC pipe of the following sizes. | | | | | |
| | **Brand :** National Polymer | | | | | |
| | **Origin:** Bangladesh | | | | | |
| 4.1 | 32 mm dia (0.90 mm) or 1-1/4" | 130 | Rft | | | |
| | | | | | | |
| **5.0** | **Drain piping insulation for VRF System** | | | | | |
| | Insulation with 13mm thick Nitrile Rubber insulation. | | | | | |
| | **Insulation Brand :**<br>Armacell/Superlon/Allflex/Copperlon/Insulflex/Armaflex/Aflex | | | | | |
| 5.1 | ø 32 mm or 1-1/4" | 130 | Rft | | | |
| | | | | | | |
| **6.0** | **Transmission/Communication/Signal cable** | | | | | |
| | **Origin & Manufacturing:** Bangladesh | | | | | |
| | **Source:** Local purchase | | | | | |
| 6.1 | 2x0.40 rm | 300 | Rft | | | |
| | | | | | | |
| **7.0** | **Refrigerant** | | | | | |
| | **Brand : Kalton/Forane Arkema/Linde** | 4 | Cyl | | | |
| | **Source:** Local purchase | | | | | |
| | **Ref Type:** R410A Gas | | | | | |
| | **Gross Weight:** 11.3 KG/Cyl | | | | | |
| | Environment Friendly | | | | | |
| | | | | | | |
| **7.1** | **Gas** | | | | | |
| 7.1.1 | Nitrogen Gas Cylinder | 4 | Cyl | | | |
| 7.1.2 | Oxygen Gas Cylinder | 1 | Cyl | | | |
| 7.1.3 | Acetylene Gas Cylinder | 1 | Cyl | | | |
| | | | | | | |
| **8.0** | Labor cost for indoors, outdoors, copper and drain pipes with insulation, control cabling, electrical connnection, flushing, pressure test and refrigerant charging | 1 | Job | | | |
| **9.0** | Materials for Consumable items | 1 | Job | | | |
| **10.0** | **Testing, Comissioning & Balancing** | 2 | JOB | | | |
| | | | | **Total Price including Vat & Tax** | | BDT - |

Community Bank Bangladesh PLC. GSD, Head Office